



PROJECT SUMMARY:

Swedish American Heart & Vascular Center

MECHANICAL, INC.

Email: maindesk@mechinc.com

Freeport Office

2279 Route 20, E.
PO Box 690
Freeport, IL 61032
Phone: (815) 235-1955
Fax: (815) 235-1940

Hillside Office

225 Fencil Lane
Hillside, IL 60162
Phone: 708-449-8080
Fax: 708-449-0378

Fox Lake Office

135 Sayton Rd, Suite 100
Fox Lake, IL 60020
Phone: (847) 973-1123
Fax: (847) 973-1169

Customer: Swedish American Hospital

Contract Amount: \$5,656,346

Location: Rockford, IL

Mechanical was the plumbing and HVAC contractor for the Swedish American Hospital addition in Rockford, IL. Completed in March 2006, the addition focuses on Heart and Vascular Care.

We installed HVAC piping including two new rooftop AHU's, heat exchangers, pumps, a steam pressure reducing valve station, clean steam boiler, condensate receivers, flash tank, reverse osmosis system, and wall fin tubes units.

Our scope also included plumbing piping and fixtures. We installed a city water meter, main RPZ, two water heaters, a softener, triplex booster system, five sump pumps, two duplex sumps, and expansion tanks. Indoor and outdoor fountain pipe and equipment systems were also installed by our team.

In the chiller building, we installed a new chiller, cooling tower, two pumps, and associated piping.

Mechanical was honored to lead the coordination of the MEP trades, for the Swedish American Hospital project.

